EXHIBIT A - PRICING PAGE

WV Division of Natural Resources - Wildlife Resources Section

Mast Tower Kit - REBID

3.1.1 Mast Tower Kit 6 ea. \$13,000.00 \$78,000.00	£13,000.00 6 ea.	Item No.	Description	Make & Model	Qty	Qty Unit	Unit Cost*	Extended Cost
Mast Tower Kit 6	6 ea.			Bluesky Mast Systems 350G XL			\$13,000.00	\$78,000.00
		1.1	Mast Tower Kit		9	ea.		

Shipping Location:

Elkins Operation Center (EOC)

738 Ward Road

Elkins, WV 26241

Dustin Legg
Vendor Authorized Representative (Print Name)

Vendor Authorized Representative Signature

11/16/2023 Date

DESIGNATED CONTACT: Vendor appoints the individual identified in this Section as the Contract Administrator and the initial point of contact for matters relating to this Contract.

Dustin / Vice President / BPI, Inc.

(Name, Title)

Dustin Legg / Vice President / BPI, Inc.

(Printed Name and Title)

102 Wimbleton Drive, Hurricane, WV 25526

(Address)

(304) 760-8909 ext 200

(Phone Number) / (Fax Number)

dlegg@bpi-gc.com

(Email Address)

CERTIFICATION AND SIGNATURE: By signing below, or submitting documentation through wvOASIS, I certify that I have reviewed this Solicitation in its entirety; that I understand the requirements, terms and conditions, and other information contained herein; that this bid, offer or proposal constitutes an offer to the State that cannot be unilaterally withdrawn; that the product or service proposed meets the mandatory requirements contained in the Solicitation for that product or service, unless otherwise stated herein; that the Vendor accepts the terms and conditions contained in the Solicitation, unless otherwise stated herein; that I am submitting this bid, offer or proposal for review and consideration; that I am authorized by the vendor to execute and submit this bid, offer, or proposal, or any documents related thereto on vendor's behalf; that I am authorized to bind the vendor in a contractual relationship; and that to the best of my knowledge, the vendor has properly registered with any State agency that may require registration.

BPI, Inc.	
(Company)	
Dustin Lega	VP
(Authorized Signature) (Representative Name, Title)	
Dustin / Vice President / BPI, Inc.	
(Printed Name and Title of Authorized Representative)	
11/16/2023	
(Date)	
(304) 760-8909 ext 200	
(Phone Number) (Fax Number)	

STATE OF WEST VIRGINIA Purchasing Division

PURCHASING AFFIDAVIT

CONSTRUCTION CONTRACTS: Under W. Va. Code § 5-22-1(i), the contracting public entity shall not award a construction contract to any bidder that is known to be in default on any monetary obligation owed to the state or a political subdivision of the state, including, but not limited to, obligations related to payroll taxes, property taxes, sales and use taxes, fire service fees, or other fines or fees.

ALL CONTRACTS: Under W. Va. Code §5A-3-10a, no contract or renewal of any contract may be awarded by the state or any of its political subdivisions to any vendor or prospective vendor when the vendor or prospective vendor or a related party to the vendor or prospective vendor is a debtor and: (1) the debt owed is an amount greater than one thousand dollars in the aggregate; or (2) the debtor is in employer default.

EXCEPTION: The prohibition listed above does not apply where a vendor has contested any tax administered pursuant to chapter eleven of the W. Va. Code, workers' compensation premium, permit fee or environmental fee or assessment and the matter has not become final or where the vendor has entered into a payment plan or agreement and the vendor is not in default of any of the provisions of such plan or agreement.

DEFINITIONS:

"Debt" means any assessment, premium, penalty, fine, tax or other amount of money owed to the state or any of its political subdivisions because of a judgment, fine, permit violation, license assessment, defaulted workers' compensation premium, penalty or other assessment presently delinquent or due and required to be paid to the state or any of its political subdivisions, including any interest or additional penalties accrued thereon.

"Employer default" means having an outstanding balance or liability to the old fund or to the uninsured employers' fund or being in policy default, as defined in W. Va. Code § 23-2c-2, failure to maintain mandatory workers' compensation coverage, or failure to fully meet its obligations as a workers' compensation self-insured employer. An employer is not in employer default if it has entered into a repayment agreement with the Insurance Commissioner and remains in compliance with the obligations under the repayment agreement.

"Related party" means a party, whether an individual, corporation, partnership, association, limited liability company or any other form or business association or other entity whatsoever, related to any vendor by blood, marriage, ownership or contract through which the party has a relationship of ownership or other interest with the vendor so that the party will actually or by effect receive or control a portion of the benefit, profit or other consideration from performance of a vendor contract with the party receiving an amount that meets or exceed five percent of the total contract amount.

AFFIRMATION: By signing this form, the vendor's authorized signer affirms and acknowledges under penalty of law for false swearing (*W. Va. Code* §61-5-3) that: (1) for construction contracts, the vendor is not in default on any monetary obligation owed to the state or a political subdivision of the state, and (2) for all other contracts, that neither vendor nor any related party owe a debt as defined above and that neither vendor nor any related party are in employer default as defined above, unless the debt or employer default is permitted under the exception above.

WITNESS THE FOLLOWING SIGNATURE:

Cody Kaso
BPI, Inc.
102 Wimbleton Drive
Hurricane WV 25526
My Commission Expires March 13, 2028

Vendor's Name: BPI, Inc.		
Authorized Signature:		Date: 11/16/2023
State of West Virginia		
County of Putnam , to-wit:		
Taken, subscribed, and sworn to before me this 16th da	ay of November	, 20 <u>23</u> .
My Commission expires March 13th	, 20 <u>28</u> .	
AFFIX SEAL HERE	NOTARY PUBLIC_	Gody Herr
OFFICIAL SEAL NOTARY PUBLIC STATE OF WEST VINGUINIA		Purchasing Affidavit (Revised 01/19/2018,



Main: 972-509-2566

Fax: 972-509-0073



www.nts.com

National Technical Systems 1701 E. Plano Pkwy. Suite 150

Plane, TX 75074

Date: 03/12/2013 Customer: BlueSky Mast Inc. 1515 Gunn Hwy. Odessa, FL 33556

Purchase Order Number: COD

A. TESTS: High Temperature, Low Temperature, Humidity, Salt Fog,

Sand and Dust, Icing & Freezing Rain

B. TEST ITEM: Mast Assembly

C. SPECIFICATION: 1. MIL-STD 810G

D. RESULTS:

This is to certify that the Mast Assembly was subjected to the High Temperature, Low Temperature, Humidity, Salt Fog, Sand and Dust, Icing & Freezing Rain tests according to the above specification.

See Page 4 for Summary of Test Results. The Mast Assembly was returned to BlueSky Mast for final evaluation.

Test data, an equipment list, and photographs are attached.

Kimberly Zavala

Preparer

John Ngo

Program Manager

Kimberly Zavala Quality Assurance

Manager

Tris report and the information constitute herein represent the results of testing test articles reported and selected by the elemperformation specifications and/or presentations, expressed or implication testing is adequate for inaloguate) to demonstrate officiery, performance, reliability, or any other characterize of the acieus from use of, examilar produces. This report photol not be refer upon as an endersoment or creditation by NTE of the equipment below, nor does it represent any statement whosever as or its more handflyer filmes of the best adds, or similar products, for a particular purpose. This report shall not promption occupy in full.



SUMMARY OF TEST RESULTS

The test program consisted of subjecting the Mast Assembly to testing described in this report. The test results are tabulated in the test summary below.


Test	Test Specification	Conforms	Test Location	Date
Low Temperature	MIL-STD 810G Method 501.4 Procedure I	Yes	NTS Plano	02/18/2013- 02/19/2013
High Temperature	MIL-STD 810G Method 502.4 Procedure I	Yes	NTS Plano	02/15/2013- 02/16/2013
Humidity	MIL-STD 810G Method 507.4 Procedure I	Yes	NTS Plano	02/20/2013- 02/21/2013
Salt Fog	MIL-STD 810G Method 509.4 Procedure i	Yes	NTS Plaņo	03/03/2013- 03/06/2013
Dust	MIL-STD 819G Method 510.4 Procedure I A	Yes	NTS Plano	02/26/2013
High Temperature Dust	MIL-STD 810G Method 510.4 Procedure I B	Yes	NTS Plano	02/27/2013
Sand	MIL-STD 810G Method 510.4 Procedure II	Yes	NTS Plano	02/28/2013
Icing Freezing Rain	MiL-STD 810G Method 521.3	Yes	NTS Plano	03/06/2013- 03/08/2013



HIGH TEMPERATURE TEST DATA

CUSTOME	Č:	BlueSky Mask Inc.	MJO: PR	019878	
TEST TIEM	-	Mast Assy	DATE: 2/1	5/13	
MODEL NU		BSMB/BSM2	UNIT NO EN		
SPECIFICA'	TION:	MEL-STD 810G	CHAMBER!		
METHOD:		501.4, Procedure: I	TECH/ENG	R: BNFB	
		DESCRIPTION OF TE	ST	1	
DATE:	TIME:	LOG ENTRY:		EUT Operate	TECHIENG INITIALS:
2/15/13	1500	Beein set up for Cyclic High Temperature Test		N/A	BNFB
	1520	EUT in stalled in chamber, photograph taken			BNFB
	1545	Berin test			BNFB
	1600	From ambiers conditions rates chamber to 35°C			BNFB
	1700	Chamber at conditions range to 34°C			BNFB
	1900	Chamber at conditions ramp to 33°C			BNFB
	2200	Chamber at conditions ramp to 36°C			BNFB
	2300	Chamber at conditions ramp to 40°C			BNFB
2/16/13	0000	Chamber at conditions rump to 44°C			BNFB
	0100	Chamber at conditions ramp to 51°C			BNFB
	0200	Chamber at conditions ramp to 56°C			BNFB
	0300	Chamber at conditions ramp to 63°C			BNFB
	0400	Chamber at conditions ranno to 69°C			BNFB
	0800	Chamber at conditions ramp to 70°C			BNFB
	0900	Chamber at conditions ramp to 67°C			BNFB
	1000	Chamber at conditions ramp to 63°C			BNFB
	1100	Chamber at conditions ramp to 55°C			BNFB
	1200	Chamber at conditions range to 48°C			BNFB
	1300	Chamber at conditions range to 41°C			BNFB
	1400	Chamber at conditions ramp to 39°C			BNFB
	1500	Chamber at conditions ramp to 37°C			BNFB
	1600	Chamber at conditions ramp to 35°C			BNFB
	1630	Test complete no anomalies noted			BNFB
		Unit conforms			BNFB
	/				








HIGH TEMPERATURE TEST EQUIPMENT LIST

NTS ID#	Manufacturer	Description	Model No.	Cal Date	Cal Due
ENV-1132-P	Thermotron	Tenny RH Chamber	WP802	N/A	N/A
ENV-1131-P	Wastow	Over-Temp Protection	SD6L	N/A	NA
ENV-1060-P	Watlow	Temp Humidity Controller	F-4	10/05/12	10/05/13
ENV-1270-P	Vaisala	Hamidity Probe	HMT 120	06/26/12	06/26/13

LOW TEMPERATURE TEST DATA

USTOMER	Ŀ	BlueSky Mask Inc.	MO:	PR01987	8	
IEST ITEM	-	Mast Asov	DATE:	2/18/13		
MODEL NU	MRER-	BSMB/BSM2	UNITNO	ENVI		
PECIFICA	· ·	MEL-STD SIOG	CHAMBI		16	
ETHOD:		502.4, Procedure: I	TECH/E		BNFB	
		DESCRIPTION	OFTEST			
DATE:	TIME:	LOGENTE	¥:		EUY Operate	TECHNENGR INTHALS:
2/18/13	1500	Besin set up for Low Temperature			N/A	BNFB
	1600	EUT in stalled in chamber, photograph tak	en			BNFB
	2130	Begin test				BNFB
	2200	From antisent conditions many chamber to	-40°C			ENFE
	2300	Raum commiste chamber at conditions son	k far 6 hours			BNFB
2/19/13	6500	Soak complete return chamber to ambient	temperature			BNFB
	0600	chamber at conditions test counlete				BNFB
		No visual anormière or damuse poted				BNFB
		Unit conforms				
				_	-	
		1				
	ICIAN/EN	GNEER: B Newtreham F Boy	DATE:		V19/13	

Bluesky Mast PR019878 Low Response




LOW TEMPERATURE TEST EQUIPMENT LIST


NIS ID#	Manufacturer	Description	Model No.	Cal Date	Cal Due
ENV-1132-P	Thermoteca	Tempità Chamber	WP802	N/A	N/A
ENV-1131-P	Watlow	Over/Temp Protection	SD6L	N/A	N/A
ENV-1060-P	Wattow	Temp Humidity Controller	F-4	10/05/12	10/05/13
ENV-1270-P	Vaisala	Hamidity Probe	HMT 120	06/26/12	06/26/13



HUMIDITY TEST DATA

USTOMER		Bine Sky		PR019878	
EST ITEM		Mast Assv		2/20/13	
DODEL NU		BSMB/BSMQ	UNIT NO:		
PECIFICA: ÆTHOD:	eron:	MS-Std S10G 507.4 Pro 1	CHAMBER TECH/ENG		
E I HUU:	_	DESCRIPTION		R EVIB	_
DATE:	TEME:	LOGENT		Terro.	TECH'ENG
			PAL.	EUT Operate	ENTRALS:
2/20/13	1630	Begin ser up for Humidity		NA	BNFB
	1615	EUT in stalled in chamber, photograph to	iken		BNFB
	1630	Begin test			BNFB
	1700	Rame to 27°C at 100% harridity			BNFB
	1720	Chamber at conditions soak for 1 hour			BNFB
	1320	Soak complete			BNFB
	1822	Rann to 26°C at 100% humidity			BNFB
	1940	Chamber at conditions soak for 4 hours			BNFB
2/21/13	0117	Soak complete Ramo to 37°C at 94% im	স্থানীয় <u> </u>		BNFB
	0220	Chamber at conditions ratio to 29°C at 8	8% munidity		BNFB
	0320	Charmber at conditions range to 31°C at 8	2% humidity		BNFB
	0420	Chamber at conditions ramp to 32°C at 7	9% humidity		BNFB
	0520	Chamber at conditions ramp to 33°C at 7	7% hundiry		BNFB
	0620	Chamber at conditions range to 34°C at 7	5% humidiry		BNFB
	0720	Chamber at conditions range to 34°C at 7	4% humidity		BNFB
	0820	Chamber at conditions ranto to 35°C at 7	4% humidire		BNFB
	0915	Chamber at conditions soak for 1 hour			BNFB
	1015	Soak complete Ramp to 34°C at 76% has	midity		BNFB
	1115	Chamber at conditions range to 33°C at 7	5% humidity		BNFB
	1215	Chamber at conditions range to 32°C at 8	2% hunsdiry		ENFB
	1315	Chamber at conditions range to 31°C at 8			BNFB
	1415	Chamber at conditions range to 29°C at 9	THE RESERVE OF THE PERSON NAMED IN COLUMN TWO IS NOT THE PERSON NAMED IN COLUMN TWO IS NOT THE PERSON NAMED IN		BNFB
	1515	Chamber at conditions range to 25°C at 9			BNFB
	1615	Chamber at conditions range to 28°C at 9	Sets et Sets Sets Sets Sets Sets Sets Se		BNFB
	1715	Chamber at conditions range to 27°C at 1			ENTE
	1315	Chamber at conditions soak for 1 hour			BNFB
	1915	Soak complete cycle 1 complete			BNFB
2/21/13	1815	Cycle 2 complete			BNFB
		Test complete return chamber to ambient	conditions		BNFB
		No physical damese or anomalies noted it			400 00 40








HUMIDITY TEST EQUIPMENT LIST

NTS ID#	Manufacturer	Description	Model No.	Cal Date	Cal Due
ENV-1046-P	Environonic	Temp/Humidity Chamber	EH-64-2-5	N/A	NA.
ENV-1067-P	Omega	Over/Tem Protection	CN76133	N/A	N/A
ENV-1025-P	Wattow	Temp Humidity Controller	F-4	12/10/12	12/10/13
ENV-1187-P	Viasala	Humidity Probe	HMT-100	10/22/12	10/22/13

SALT FOG TEST DATA

CUSTOMER	-	Bhasky N					019978	
EST FIEM:		Mast Assy					13	
TODET MA	MBER:	BSMI-BS				UNII NO: EN		
PECIFICAT	TION:	MIL-STD				CHAMBER N		
JETHOD:		509.4 Proc				TECH ENGR:	BNTB	
Type of		Food grad	-	Type of V		Type 4 De-ioniz	ed	
Salt (Concentrati	ieta.	536	Water Cond		-SpS:rm		
			Rend	ings Belevo to be 8	onitared Dai	l v		
DATES	TIME	Temp 38C (+/-2C)	Falland Rate I.	O to 3.9 ml. bour	Ph 6.5 to 7.2 of Collection	Specific Gravi Collection 1.0 1.049		TECH /
3/3/2013	1530	34°C	1.5 m	Lhour	6.6 Ph	1.035	1	BN/FB
3.4/2013	1530	35°C	1.9 m	Lhone	6.8 Ph	1.03\$	2	BN TB
					777			
				9				
			.1	PARTITION	OF TEST			
DATE:	TIME:			EUT Operates	TECH/ ENGR:			
3/2/13	0300	Begin test	set up for Salt F	CE			N/A	BNFB
	0310	EUT instal	ied in chamber a	hotograph taken				BN/FB
	OSIS	Coeration	verified begin to	St.				BNFB
		Condeien d	indicion chamber to 35°C. for 2 hours before introducio		star gnisution			BN FB
	1026	2 hour cond	ecelomes eninosal	ventled udtAvates t	acious race of 2	1 mVWOces2Aur		BNFB
	1025	Continue sa	à for for an additi	onal 48 hours				BMFB
3/4/13	1025	-		17 from chamber an	d allow 48 hm	r davne periodi		BNTB
3/6/33	1025	-	ins period comple					BN/FB
	1030	_		al no excessive aut	danninge notes	, moves freely		EN/FB
		ides confor			-			

BlueSky Mast PR019878 SaltFog





SALT FOG TEST EQUIPMENT LIST

NISID#	Mannfacturer	Description	Model No.	Cal Date	Cal Due
ENV-1218-P	NIS	Salt-Fog Chamber	Large	N/A	N/A
ENV-1128-P	Wailew	Temperature Controller	F4	10/5/2012	10/5/2013
ENV-1219-P	Omega	HiLow Limit	CIN76000	N/A	N/A



SALT FOG TEST SETUP



SALT FOG POST TEST





SALT FOG POST TEST



SALT FOG POST TEST





SALT FOG POST TEST – AFTER 48 HOUR DRYING PERIOD/CLEANING



SALT FOG POST TEST – AFTER 48 HOUR DRYING PERIOD/CLEANING



SALT FOG POST TEST - AFTER 48 HOUR DRYING PERIOD/CLEANING




DUST TEST DATA

CUSTOMER	Ŀ	HingSky Mask Inc.	MJO: P	R019878		
EST ITEM		Mast Assy		/26/13		
JODEL NU	MBER-	NA UNIT NO: ENVI MIL-STD 810G CHAMBER NO: I		NVI	O: Dust 48	
PECIFICAT	TEON:					
METHOD:		510.4, Procedure: 1 A. TECH / ENGR:		R BN FB	BN/FB	
	-	DESCRIPTION OF TEST				
DATE:	TEME:	LOG ENTRY:		EUT Operate	TECHLENGE INTITALS:	
2/26/13 0930 0945		Begin test set up for Ambiem Dust Dust rate set at 10.6=# 7 grams per cubic meter			BNFB	
	1000	Installed EUT in dust chamber.			BNFB	
	1005	Ease of operation of all moving parts verified		I	BNIB	
	1010	Took photo of test set up.			BNFB	
	1015.	Begin test wind speed at 3.7 m/s			BWFB	
	1020	Chamber temperature stable 25°C Begin 6 hour b	dowing dust.		BNFB	
		Relative humidity below 30%			BWIB	
	1620	5 hour blowing dust complete. Stop that feed.			BNFB	
	1625	Test item stable at ambient termerature			BNFB	
	1630	Removed excess dust from unit with soft bristle t	मग्रदी:		BNFB	
	1632	Performed ease of operation of all moving parts v	rerified	x	BN/FB	
		No anomalies noted unit conforms			BN/FB	
		Dust used was Red China Clay				
CHNICIAN	M ANGINIA	E B Newingham F Boyd		DATE:	2/26/13	

DUST TEST EQUIPMENT LIST

NTS ID#	Manufacturer	Description	Model No.	Cal Date	Cal Due
ENV-1235-P	NTS	Dust/Sand Chamber	NIS	N/A	N/A
ENV-1340-P	Almor	Hot wire Anemometer	AVM 430	07/24/12	07/24/13
ENV-1254-P	Omega	Hi-Lo Limit	CN76000	N/A	N/A
ENV-1253-P	Watlow	Temp Centroller	F4	12/10/12	12/10/13
ENV-1234-P	Viasalia	Humidity Probe	HMT 100	05/25/12	05/25/13

PR019878 BlueSky Mast AusbiantDust






HIGH TEMPERATURE DUST TEST DATA

Chat(0)/in:	Ŀ	BhieSky Mask Inc.	MJO:	PR019578		
TEST TEFA		Mast Assy	DATE:	2/27/13		
MODEL NUMBER: SPECIFICATION: METEOD:		NA ·	UNIT NO	UNIT NO: ENVI		
		MIL-STD S10G CHAMBER NO: 510.4, Procedure: 1 B TECH / ENGR:		ER NO: Dust 48		
				NGR: ENFB		
		DESCRIPTION OF T	est			
DATE:	TIME:	LOG ENTRY:		EUT Operate	TECHTENGI INITIALS:	
2/27/13 0800		Begin test set up for High Temperature Dust			BNFB	
	0810	Installed EUT in dust chamber.			ENFB	
		Dust rate set at 10.5==/- 7 grams per cubic meter				
	0811	Ease of operation of all moving parts verifies	ase of operation of all moving parts verified		ENFB	
	0813	Fook photo of test set up.			BN/FB	
	0815	Begin test ramp chamber to 70°C wind speed at 1.5m/s			BN/FB	
	1055	Chamber temperature stable 70°C Begin 6 hour blowing dust.			ENTE	
		wind speed at 8.8m/s Relative humidiry below 30%.			BNFB	
	1655	5 hour blowing dust complete. Stop dust feed. Return to ambient		ient	BNFB	
	1710	Text stem stable at ambient temperature			BN/FB	
	1712	Removed excess dust from unit with soft bri	tie brush		BN/FB	
	1715	Performed ease of operation of all moving pa	ats verified	2	BN/FB	
		No mornalies noted unit conforms			BN/FB	
		Dust used was Red China Clav				
CHNICIAN	FNGINE	E B Newinsham F Bo	riî	DATE:	2/27/13	

PR019878 BlueSky Mast



HIGH TEMPERATURE DUST TEST EQUIPMENT LIST

NIS ID#	Manufacturer	Description	Model No.	Cal Date	Cal Due
ENV-1235-P	NTS	· Dust Sand Chamber	NTS	N/A	N/A
ENV1340P	Alner	Fot wire Anemometer	AVM 430	07/24/12	07/24/13
ENV-1254-P	Omesa	Hi-Lo Limit	CN76000	N/A	N/A
ENV-1253-P	Wastow	Tenuo Controller	F4	12/10/72	12/10/13
ENV-1234-P	Viasalla	Humidity Probe	HMI 100	05/25/32	05/25/13





HIGH TEMPERATURE DUST TEST SETUP




HIGH TEMPERATURE DUST POST TEST



SAND TEST DATA

CUSTOMER:		BhieSky Mask Inc.	MIO:	PRD19878	
TEST FIEM: MODEL NUMBER: .		Mast Assy	DATE:	2/28/13	
		NA UNIT NO:		ENVI	
SPECIFICAT	TON:	MIL-STD 810G		RNO: Sand 48	
AFTHOD:		510A, Procedure: II	TECH/E	NGR: BN/FB	
		DESCRIPTION OF TEST			
DATE:	TIME:	LOGENTRY:		EUT Operate	TECHNENGR INITIALS:
2/28/13	0750	Chamber controls set at 2.1 grams sand per cubic meter			BN/FB
- A		wind speed set at 10m/s			BNFB
	0820	Begin test set up for High Temperature Sand			BN/FB
1	0830	Installed EUT in sand chamber.			BNFB
,	0840	Ease of operation of all moving parts verified		Ī	BNFB
	.0845	Took photo of test set up.			BN/FB
ja ja	0925	Begin test rame chamber to 70°C			BNFB
	1125	Chamber temperature stable 70°C Begin 6 hour ble	has enter		ENFB
		Relative humiday below 30%			BNFB
	1725	6 hour blowing sand complete. Stop sand feed. Re	turn to amb	ent	BN/FB
	1740	Test items stable at ambient temperature.			BNFB
	1742	Removed excess sand from unit with soft bristle by	ush		BN/FB
	1745	Performed ease of operation of all moving parts ve	rified	1	BNFB
1		No anomalies noted unit conforms			
ECHNICIA!	N/ENGINEE	B Newingham F Boyd		DATE:	2/28/13


PR019878 BlueSky Mast High Temperature Stand



SAND TEST EQUIPMENT LIST

NTS ID#	Mannfacturer :	Description	Model No.	Cal Date	Cal Due
ENV-1235-P	NIS	Dust-Sand Chamber	NTS	N/A	N/A
ENV1340P	Alnor	Flot wire Anamometer	AVM 430	07/24/12	07/24/13
ENV-1254-P	Omega	Hi-Lo Limit	CN76000	NA	N/A
ENV-1253-P	Watiow	Temp Controller	F4	12/10/12	12/10/13
ENV-1234-P	Viasalla	Humidity Probe	HMT 100	05/25/12	05/25/13





SAND TEST SETUP




SAND POST TEST



ICING AND FREEZING RAIN TEST DATA

CUSTOMER	: :	BhaSky Mask Inc.	MJO:	PR019878		
TEST ITEM		Mast Asry .	DATE:	3/5/13		
MODELNU	MBER:	BSMI-BSM2 UNIT NO: ENVI		ENVI		
SPECIFICATION:		MII-STD 810G CHAMBER NO:		12		
METHOD:		521.3 TECH / ENGR:		BN/FB		
		CI	RITERIA			
		DESCRIP	tion of test			
DATE:	TIME:	LOG ENTRY:		EUT Operational	TECHENGI INTITALS:	
3/6/33 1000		Begin tout set up for Icing Freezing !	lain			BN/FB
	1035	Installed EUT in Chamber				BNTE
1030	1030	Ease of operation of all moving parts verified			3	BN/FB
	1050	Begin test				BNTB
	1133	Chamber temperature stabilized at 0°C start watering for I hour				BNFB
	1213	1 Hour pre spraying complete adjust chamber to -10°C				BNFB
	1222	Chamber at conditions, continue icing until .25" of its has been achieved				BNTB
3/B/33	1030	Tre at .25" stop icing at this time and allow ice to harden for 4 hears.				BNFB
	1430	4 Hour ice hardwing complete, open	ational check attenue was	accessful.		BNFB
		used small subber timped hammer to	squicte ice second attenu	t voscessful	K	BNFB
	1440	Return chamber to ambient condition	u and allow for de thawir	5		BNFB
	1506	Chamber at conditions EUT has been	thawed			BNFB
1	1510	Operational check satisfactory			x	BNFB
	CLAN / EN	Test complete				

BlueSky Mast PR019878



ICING AND FREEZING RAIN TEST EQUIPMENT LIST

NIS ID#	Manufacturer	Description	Model No.	Cal Date	CalDue
ENV-1076-P	Russell	Temp Humidity Chamber	ECM 3-30-30	N/A	N/A
ENV-1040-P	Omega	Over/Tem Protection	CN76133	N/A	NA
ENV-1258-P	Watłow	Temp Humidity Controller	F-4	10/05/12	10/05/13
ENV-1196-P	Viasalia	Hamidity Probe	HMT 100	03/23/12	03/23/13





ICING AND FREEZING RAIN TEST SETUP



ICING AND FREEZING RAIN - 0.25" OF ICE



GSA Schedule

SCHEDULE GS-07F-59IGR

350G XL Lift Series - Disclaimers and Warranties

DISCLAIMER OF WARRANTIES AND LIABILITY

DO NOT ATTEMPT TO DEPLOY THIS MAST IF YOU ARE NOT EXPERIENCED IN SIMILAR DEVICES

You are responsible for your own safety and survival and that of those persons around the mast. This manual is to be used as an aid and only to be used at your own risk. Nothing will replace good sound judgment when deploying the mast.

The information provided in this manual should be used as a guideline and not absolute fact. Many variables are involved in deploying a mast system such as weather, soil conditions, guying distances, cantilevered payloads, surrounding obstacles, accuracy and precision of guying, etc.

BLUESKY MAST, INC. MAKES NO WARRANTIES REGARDING THE GOODS, EXPRESS OR IMPLIED, INCLUDING WARRANTY OF MERCHANTABILITY OR WARRANTY OF FITNESS FOR A PARTICULAR PURPOSE. BUYER MAKES NO RELIANCE ON ANY REPRESENTATION OR DOCUMENTATION OF BLUESKY MAST, INC., EXPRESS OR IMPLIED, WITH REGARD TO THE GOODS.

BLUESKY MAST, INC. SELLS THE GOODS TO BUYER ON CONDITION THAT BLUESKY MAST, INC. WILL HAVE NO LIABILITY OF ANY KIND AS A RESULT OF THE SALE. BUYER AGREES THAT BLUESKY MAST, INC. SHALL HAVE NO LIABILITY FOR DAMAGES OF ANY KIND, WHETHER DIRECT, INCIDENTAL OR CONSEQUENTIAL DAMAGES, INCLUDING INJURIES OR DEATH TO PERSONS OR PROPERTY, TO BUYER, ITS EMPLOYEES, CUSTOMERS OR AGENTS, AS A RESULT OF THE SALE. BUYER ALSO AGREES TO HOLD BLUESKY MAST, INC. HARMLESS FROM ANY CLAIMS BUYER, OR ANY THIRD PARTY, MAY HAVE AS A RESULT OF BUYER'S USE OF THE GOODS.

BUYER HAS READ THIS DISCLAIMER AND AGREES WITH ITS TERMS IN CONSIDERATION OF RECEIVING THE GOODS.

REPORTING ERRORS AND RECOMMENDING IMPROVEMENTS

If you find any mistakes or you can help improve this material, please contact BlueSky Mast via US Mail at:

BlueSky Mast Inc 2080 Wild Acres Road Largo, FL 33771 USA

Or

Phone: 877-411-6278

Fax: 866-411-6278

email: support@blueskymast.com

Cage Code: 3JWX5

DUNS Number: 137469404



350G XL Lift Series - Disclaimers and Warranties

LIMITED TWELVE MONTH WARRANTY

This BLUESKY MAST, INC. equipment is warranted to be free from defects in material and workmanship under normal use and service. BLUESKY MAST, INC. shall repair or replace defective equipment, at no charge, or at its option, refund the purchase price, if the equipment is returned to BLUESKY MAST, INC. not more than twelve (12) months after shipment. Removal or reinstallation of equipment and its transportation shall not be at the cost of BLUESKY MAST, INC. except BLUESKY MAST, INC. shall return repaired or replaced equipment freight prepaid to a continental United States address.

This Warranty shall not apply to equipment which has been repaired or altered in any way so as to affect its stability or durability, or which has been subject to misuse, negligence or accident. This Warranty does not cover equipment which has been impaired by severe weather conditions such as excessive wind, ice, storms, lightning, or other natural occurrences over which BLUESKY MAST, INC. has no control, and this Warranty shall not apply to equipment which has been operated or installed other than in accordance with the instructions furnished by BLUESKY MAST, INC.

Products are manufactured from anodized aluminum in various colors. Color fading and varying shades of color will inevitably occur with exposure to sunlight and environmental conditions and is not considered a defect in the material or product

Claimants under this Warranty shall present their claims along with the defective equipment to BLUESKY MAST, INC. immediately upon failure.

Noncompliance with any part of this claim procedure may invalidate this warranty in whole or in part.

This warranty is expressly in lieu of all other agreements and warranties, any implied warranty of merchantability or fitness for a particular purpose is limited in duration to the duration of this warranty. BLUESKY MAST, INC. Neither assumes nor authorizes any representative or other person to assume for it any other liability in connection with the equipment delivered or provided. In no event shall BLUESKY MAST, INC. Be liable for any loss of profits, loss of use, interruption of business, or indirect, special or consequential damages of any kind.

In no event shall BLUESKY MAST, INC. be liable for damages in an amount greater than the purchase price of the equipment. Some states do not allow limitations on how long an implied warranty lasts, or allow the exclusion or limitation of incidental or consequential damages, so the above limitations or exclusions may not apply to you.





350G XL Lift Series - Safety Warnings

IMPORTANT SAFETY PRECAUTIONS

Part I: Power Lines, Lightning and Grounding

- LOOK UP AND LIVE! Before erecting the mast, check for overhead power lines. Never deploy this mast where there is any possibility of direct or indirect contact with a power line. Keep the mast a distance equal to or greater than twice its height away from power lines. This will ensure that the Antenna, masts, guy ropes or cables will not contact power if it falls either during installation or later. Any person touching any part of a mast or even standing near a mast that contacts a power line can be seriously injured or killed.
- BEWARE OF UNDERGROUND POWER LINES! Ground stakes might penetrate underground
 power lines. Before deploying any ground stakes, be sure to check the area for warnings of buried cables and contact your local power company to verify. Any person touching any part of a
 mast or even standing near a mast that contacts a power line can be seriously injured or killed.
- Keep guy ropes away from power lines to eliminate the possibility of a power line falling on the guy rope.
- Never touch a mast or structure that you suspect may be accidentally energized electrically.
- Never work with a mast or related structure during electrical storm activity.
- Contrary to popular belief, most lightning injuries and damage do not come from direct lightning strikes. There are several ways that lightning can injure you:
- "Step Potential" is potentially hazardous voltage that can exist on the ground like stepping on a
 live wire. This results from electrical energy diverted into the ground from lightning striking
 nearby. It is the most common injury causing lightning effect.
- Flashover is when lightning strikes a nearby object and then jumps to another nearby object.
 This is usually what injures people standing under trees in an electrical storm.
- Do not stand near the mast, deploy or retract the mast during electrical storm activity.
- Always ground the mast.



350G XL Lift Series - Safety Warnings

IMPORTANT SAFETY PRECAUTIONS

Part II: Guy Ropes and Fasteners

- Inspect all guy ropes and fasteners for wear or damage before use. Serious injury or death may
 occur if a guy rope failure causes a mast to fall.
- Mark guy ropes clearly to prevent personnel from tripping over them. Personnel who trip may suffer injury and may also pull up a guy rope and cause the mast to fall.
- Monitor the tension of the guy ropes to ensure proper tension.
- Ensure that stakes and anchors are secure in the ground before attaching guy ropes. Use extra caution when anchoring guy ropes, especially in sandy or loose soil.
- Never fasten a guy rope over a sharp edge or in a manner that causes abrasion. This may cause guy rope failure. Pad any contacting surfaces if necessary.
- Do not install guy ropes across roadways or other paths of travel. Always clearly mark guy ropes.
- Ensure guy ropes are clear of branches and other obstructions.
- Use only authorized parts. Unapproved substitutes may not be strong enough for the equipment.
- Periodically inspect the mast to ensure that it remains structurally sound and properly installed.
- Never overload the mast or structure. Use ONLY the equipment and accessories in proper quantities as described by the manufacture specifications. Do not use unauthorized equipment or modifications.
- BE CAUTIOUS of ice that may form on the antenna/mast. The area around the antenna/mast should be marked and roped off to avoid falling ice. Special care must be taken when retracting the mast or structure to avoid falling ice.
- Use additional guy ropes for the mast, if heavy ice loading or wind is expected or anticipated.
- Ensure that the wind speed is not excessive during deployment/retraction operations. Maximum safe wind speeds are available from manufacturer for your specific mast.





350G XL Lift Series - Safety Warnings

IMPORTANT SAFETY PRECAUTIONS

Part III: Wind Conditions

- BlueSky Mast recommends that you do not to attempt to actively deploy in winds that exceed 10
 mph with Novice Users, 15 mph with Intermediate Users and 20 mph with Expert Users.
- During windy conditions it will be necessary to incrementally guy the mast as it is being deployed.
- Incremental Guying will add time to the deployment but increase the protection of personnel and equipment.

USE THE CHART BELOW TO HELP DETERMINE WIND SPEED

VISUAL OBSERVATIONS	КМ/Н	МРН	DEPLOYMENT CONDITIONS
Smoke Rises Vertically	<1	<1	Safe
Wind Direction Shown by Smoke	1-6	1-3	Safe
Wind Felt on Face, Leaves Rustle	7-12	4-7	Safe
Leaves & Twigs in Constant Motion, Wind Extends Light Flag	13-18	8-11	Use Caution
Dust and Loose Paper Blown Freely, Small Branched Move	19-26	12-15	Use Caution
Small Trees Begin to Sway	27-35	16-22	Dangerous Conditions
Large Branches in Motion, Wind Whistles Through Wires	36-44	23-27	Dangerous Conditions
Whole Trees in Motion	45-55	28-34	Dangerous Conditions



Deployable Payload

A mast installation can be exposed to several types of loads. The physical weight of the instrument and its attachments is referred to as the payload. The mast can support much more weight when properly guyed and stabilized but BlueSky Masts will only recommend payloads that are safe to carry during the deployment process and we call this the deployable load. The remaining reserve load capacity represents the margin designed to absorb any subsequent environmental load that the mast may encounter. The primary environmental load on a mast is wind load.

The payload capacity on a BlueSky Mast is governed by the installer's ability to safely elevate the payload to the desired height. As poles are inserted into the tripod and the mast begins to climb, the mast tip has a tendency to lean off-center and away from its position of greatest strength. An iterative process of incremental guying and mast pole elevation may be required to successfully deploy the mast. For best results, please limit your deployment to the height and payload combinations given in the table below.


350G XL - Lift Series	Deployable Load (lbs.)	Wind Load (Primary and Secondary Guying)
15 M (49 ft.)	75 lbs.	90 MPH
14 M (45.5 ft.)	85 lbs.	90 MPH
13 M (42 ft.)	95 lbs.	90 MPH
12 M (38.5 ft.)	105lbs.	90 MPH
11 M (35 ft.)	115 lbs.	90 MPH
10 M (31.5 ft.)	125 lbs.	90 MPH
8 M (28 ft.)	145 lbs.	90 MPH



Wind Effects

When wind blows on a mast and its instruments, the guys restrict the top of the mast and its instruments from moving off center. The mast's reaction to wind will put tension in the guy line and force the top of the mast downward in compression, the amount of which will vary depending on the anchor distance as described below.

The size and shape of the instruments determine the amount of force they produce in any given wind condition. Don't forget that the mast itself is a surface area exposed to the wind and its wind load will need to be added to the instrument wind load to get the total wind load on the system. The mast wind loads are given in the table at the end of this section and clearly show the benefits of Secondary Guying.




Guying

Guy lines are used to maintain the position of the top of the mast directly over the center of the tripod. This is its position of greatest strength, which will maximize the load carrying capacity of the mast in terms of payload as well as wind survivability. When no wind is present, the guy lines remain critical to stabilize the top of the mast and to keep the instrument mounts level.



Anchor Radius


Ideal guying is set with an anchor radius of 80% of the total mast height. Many applications of mast deployments are not able to afford an installation footprint of this size and installers may find it more convenient to place the guy anchors much closer to the mast as shown in the figure to the right. BlueSky Mast does not recommend configurations utilizing less than 80% guy radius, but if your site dictates that you must deviate from the recommended configuration it is imperative that the installer is aware of the effects of the reduced anchor radius and its effect on total payload capacity and wind loading.



The angle of pull on the guy line relative to the anchor radius may produce a lever effect increasing the mast compression due to wind loading by a factor of 5!

Guying Distance	Anchor
(% of Mast	Radius
Height)	Factor
10%	10.00
20%	5.00
30%	3.33
40%	2.50
50%	2.00
60%	1.67
70%	1.43
80%	1.25
90%	1.11
100%	1.00

The table at left shows the affect the anchor radius has on the multiplying factors of compressive loads produced on the mast by a horizontal wind force. Below is the recommended 80% guy radius.





Primary and Secondary Guy Placement


BlueSky utilizes a 4 guy configuration with a guying distance of 80% the total height of the mast to help minimize the affect wind loading has on the mast. The primary guys are always deployed from the top of the mast and extend out at a 90 degree angle from each other. Primary guy ropes are attached to the top hole of the large guy stake.


The secondary guys are deployed halfway down the mast between the top of the tripod and the primary guys. They are also deployed at 90 degrees of each other and are attached to second hole, under the primary guy ropes on the large guy stake.

Primary Guy Placement (Top Hole of Large Guy Stake)



Secondary Guy Placement (Bottom Hole of Large Guy Stake)





Guying Distance From the Base of the Mast

If you are unable to utilize the 80% rule then refer to the load characteristics of your mast in the tables following this section to understand the impact to the payload capacity and wind loading of your mast.



15 Meter System - Specifications

Fully Operational	Survivable	Mast I	ailure			
1!	5 Meter 350G Ma	st				
Primary Guying Only Assumes tripod and guys are properly secured, soil conditions can greatly affect the holding capability of guy stakes						
	75 Lbs. Deployed					
Wind Spe	eed (mph)	70	90			
	30% Guy Distance					
1 Sq. Ft. Panel	50% Guy Distance					
	80% Guy Distance					
	30% Guy Distance					
2 Sq. Ft. Panel	50% Guy Distance					
	80% Guy Distance		الساهيا			
	30% Guy Distance					
3 Sq. Ft. Panel	50% Guy Distance					
	80% Guy Distance					
	30% Guy Distance					
4 Sq. Ft. Panel	50% Guy Distance					
	80% Guy Distance					

Fully Operational	Survivable	Mast	Failure		
1	15 Meter 350G Mast				
Primary & Secondary Guying Assumes tripod and guys are properly secured, soil conditions can greatly affect the holding capability of guy stakes					
	75 Lbs. Deployed				
Wind Sp	eed (mph)	70	90		
	30% Guy Distance				
1 Sq. Ft. Panel	50% Guy Distance				
	80% Guy Distance				
	30% Guy Distance				
2 Sq. Ft. Panel	50% Guy Distance				
	80% Guy Distance				
	30% Guy Distance				
3 Sq. Ft. Panel	50% Guy Distance				
	80% Guy Distance				
	30% Guy Distance		L. IN		
4 Sq. Ft. Panel	50% Guy Distance				
	80% Guy Distance				

14 Meter System - Specifications

Fully Operational	Survivable	Mast F	ailure	
14 Meter 350G Mast				
Primary Guying Only Assumes tripod and guys are properly secured, soil conditions can greatly affect the holding capability of guy stakes				
	85 Lbs. Deployed			
Wind Sp	eed (mph)	70	90	
	30% Guy Distance			
1 Sq. Ft. Panel	50% Guy Distance			
	80% Guy Distance			
	30% Guy Distance			
2 Sq. Ft. Panel	50% Guy Distance			
	80% Guy Distance			
	30% Guy Distance			
3 Sq. Ft. Panel	50% Guy Distance			
	80% Guy Distance			
	30% Guy Distance			
4 Sq. Ft. Panel	50% Guy Distance			
	80% Guy Distance			

Fully Operational	Survivable	Mast I	Failure
14	4 Meter 350G Ma	st	
Primary & Secondary Guying Assumes tripod and guys are properly secured, soil conditions can greatly affect the holding capability of guy stakes			
	85 Lbs. Deployed		
Wind Spe	eed (mph)	70	90
	30% Guy Distance		
1 Sq. Ft. Panel	50% Guy Distance		
	80% Guy Distance		
	30% Guy Distance		
2 Sq. Ft. Panel	50% Guy Distance		
	80% Guy Distance		
	30% Guy Distance		
3 Sq. Ft. Panel	50% Guy Distance		
	80% Guy Distance		
	30% Guy Distance		
4 Sq. Ft. Panel	50% Guy Distance		
	80% Guy Distance		/**



13 Meter System - Specifications

Fully Operational	Survivable	Mast Failure		
13 Meter 350G Mast				
Primary Guying Only Assumes tripod and guys are properly secured, soil conditions can greatly affect the holding capability of guy stakes				
	95 Lbs. Deployed			
Wind Spo	eed (mph)	70	90	
	30% Guy Distance			
1 Sq. Ft. Panel	50% Guy Distance			
	80% Guy Distance			
	30% Guy Distance			
2 Sq. Ft. Panel	50% Guy Distance			
	80% Guy Distance			
	30% Guy Distance			
3 Sq. Ft. Panel	50% Guy Distance			
	80% Guy Distance			
	30% Guy Distance			
4 Sq. Ft. Panel	50% Guy Distance			
	80% Guy Distance			

Fully Operational	Survivable	Mast i	ailure	
13	3 Meter 350G Ma	st		
Primary & Secondary Guying Assumes tripod and guys are properly secured, soll conditions can greatly affect the holding capability of guy stakes				
	95 Lbs. Deployed			
Wind Sp	eed (mph)	70	90	
1 Sq. Ft. Panel	30% Guy Distance 50% Guy Distance 80% Guy Distance			
2 Sq. Ft. Panel	30% Guy Distance 50% Guy Distance 80% Guy Distance			
3 Sq. Ft. Panel	30% Guy Distance 50% Guy Distance 80% Guy Distance			
4 Sq. Ft. Panel	30% Guy Distance 50% Guy Distance 80% Guy Distance			

12 Meter System - Specifications

Fully Operational	Survivable	Mast Failure		
12 Meter 350G Mast				
Primary Guying Only Assumes tripod and guys are properly secured, soil conditions can greatly affect the holding capability of guy stakes				
1	LO5 Lbs. Deployed			
Wind Spe	eed (mph)	70	90	
1 Sq. Ft. Panel	30% Guy Distance 50% Guy Distance 80% Guy Distance			
2 Sq. Ft. Panel	30% Guy Distance 50% Guy Distance 80% Guy Distance			
3 Sq. Ft. Panel	30% Guy Distance 50% Guy Distance 80% Guy Distance			
4 Sq. Ft. Panel	30% Guy Distance 50% Guy Distance 80% Guy Distance			

Fully Operational	Survivable	Mast f	ailure	
12 Meter 350G Mast				
Primary & Secondary Guying Assumes tripod and guys are properly secured, soil conditions can greatly affect the holding capability of guy stakes				
	105 Lbs. Deployed	<u> </u>		
Wind Spe	eed (mph)	70	90	
	30% Guy Distance			
1 Sq. Ft. Panel	50% Guy Distance			
	80% Guy Distance			
	30% Guy Distance			
2 Sq. Ft. Panel	50% Guy Distance			
	80% Guy Distance			
	30% Guy Distance			
3 Sq. Ft. Panel	50% Guy Distance			
	80% Guy Distance			
	30% Guy Distance			
4 Šq. Ft. Panel	50% Guy Distance			
	80% Guy Distance		2	



11 Meter System - Specifications

Fully Operational	Survivable	Mast F	ailure		
1	11 Meter 350G Mast				
Primary Guying Only Assumes tripod and guys are properly secured, soil conditions can greatly affect the holding capability of guy states					
	115 Lbs. Deployed				
Wind Sp	eed (mph)	70	90		
	30% Guy Distance				
1 Sq. Ft. Panel	50% Guy Distance				
	80% Guy Distance				
	30% Guy Distance	W 100			
2 Sq. Ft. Panel	50% Guy Distance	أأحدا			
	80% Guy Distance				
	30% Guy Distance				
3 Sq. Ft. Panel	50% Guy Distance				
	80% Guy Distance	Les C			
	30% Guy Distance				
4 Sq. Ft. Panel	50% Guy Distance				
	80% Guy Distance				

Fully Operational	Survivable	Mast I	ailure	
1:	1 Meter 350G Ma	st		
Primary & Secondary Guying Assumes tripod and guys are properly secured, soil conditions can greatly affect the holding capability of guy stakes				
	115 Lbs. Deployed	Ī		
Wind Spo	eed (mph)	70	90	
	30% Guy Distance			
1 Sq. Ft. Panel	50% Guy Distance			
	80% Guy Distance		10	
	30% Guy Distance			
2 Sq. Ft. Panel	50% Guy Distance			
	80% Guy Distance	K 3 LS		
	30% Guy Distance			
3 Sq. Ft. Panel	50% Guy Distance			
	80% Guy Distance			
	30% Guy Distance			
4 Sq. Ft. Panel	50% Guy Distance			
	80% Guy Distance			

10 Meter System - Specifications

Fully Operational	Survivable	Mast	Failure		
1	10 Meter 350G Mast				
Pri	imary Guying Or	ılv			
Assumes tripod and guys a	ore properly secured, soil condit holding capability of guy stakes	dons can great	ly affect the		
1	7, 100				
	125 Lbs. Deployed				
Wind Sp	eed (mph)	70	90		
	30% Guy Distance				
1 Sq. Ft. Panel	50% Guy Distance				
	80% Guy Distance				
	30% Guy Distance				
2 Sq. Ft. Panel	50% Guy Distance				
	80% Guy Distance				
	30% Guy Distance				
3 Sq. Ft. Panel	50% Guy Distance	No.	ومبطا		
	80% Guy Distance				
	30% Guy Distance				
4 Sq. Ft. Panel	50% Guy Distance				
	80% Guy Distance				

Fully Operational	Survivable	Mast I	ailure	
10 Meter 350G Mast				
Primary & Secondary Guying Assumes tripod and guys are properly secured, soll conditions can greatly affect the holding capability of guy stakes				
	125 Lbs. Deployed			
Wind Sp	eed (mph)	70	90	
	30% Guy Distance			
1 Sq. Ft. Panel	50% Guy Distance			
	80% Guy Distance			
	30% Guy Distance			
2 Sq. Ft. Panel	50% Guy Distance			
	80% Guy Distance			
	30% Guy Distance	77.0		
3 Sq. Ft. Panel	50% Guy Distance			
	80% Guy Distance			
	30% Guy Distance			
4 Sq. Ft. Panel	50% Guy Distance		النطاا	
	80% Guy Distance			



8 Meter System - Specifications

Fully Operational	Survivable	Mast F	ailure	
8 Meter 350G Mast				
Primary Guying Only Assumes tripod and guys are properly secured, soil conditions can greatly affect the holding capability of guy stakes				
	145 Lbs. Deployed			
Wind Sp	eed (mph)	70	90	
	30% Guy Distance			
1 Sq. Ft. Panel	50% Guy Distance			
	80% Guy Distance			
	30% Guy Distance			
2 Sq. Ft. Panel	50% Guy Distance			
	80% Guy Distance			
	30% Guy Distance			
3 Sq. Ft. Panel	50% Guy Distance			
	80% Guy Distance			
	30% Guy Distance			
4 Sq. Ft. Panel	50% Guy Distance			
	80% Guy Distance			

Fully Operational	Survivable	Mast F	ailure
8 Meter 350G Mast			
Primary & Secondary Guying Assumes tripod and guys are properly secured, soil conditions can greatly affect the holding capability of guy stakes			
1	45 Lbs. Deployed		
Wind Spe	ed (mph)	70	90
	30% Guy Distance		
1 Sq. Ft. Panel	50% Guy Distance		
	80% Guy Distance		
	30% Guy Distance		
2 Sq. Ft. Panel	50% Guy Distance		
	80% Guy Distance	انسسا	
	30% Guy Distance		
3 Sq. Ft. Panel	50% Guy Distance		
	80% Guy Distance		
	30% Guy Distance	ستسا	
4 Sq. Ft. Panel	50% Guy Distance		
	80% Guy Distance		

7 Meter System - Specifications

Fully Operational	Survivable	Mast f	ailure
7 Meter 350G Mast			
Primary Guying Only Assumes tripod and guys are properly secured, soil conditions can greatly affect the holding capability of guy stakes			
<u> </u>	155 Lbs. Deployed		
Wind Spe	eed (mph)	70	90
	30% Guy Distance		
1 Sq. Ft. Panel	50% Guy Distance		
	80% Guy Distance		
	30% Guy Distance		
2 Sq. Ft. Panel	50% Guy Distance		
	80% Guy Distance		THE P
	30% Guy Distance		
3 Sq. Ft. Panel	50% Guy Distance		
	80% Guy Distance		1
	30% Guy Distance		
4 Sq. Ft. Panel	50% Guy Distance		
	80% Guy Distance		

Fully Ogranationes	Survivable	Mast f	ailure
7 Meter 350G Mast			
Primary & Secondary Guying Assumes tripod and guys are properly secured, soll conditions can greatly affect the holding capability of guy stakes			
	155 Lbs. Deployed	l	
Wind Spe	eed (mph)	70	90
	30% Guy Distance		
1 Sq. Ft. Panel	50% Guy Distance		
	80% Guy Distance		
	30% Guy Distance		
2 Sq. Ft. Panel	50% Guy Distance		
	80% Guy Distance		
	30% Guy Distance		
3 Sq. Ft. Panel	50% Guy Distance		
	80% Guy Distance		
	30% Guy Distance		
4 Sq. Ft. Panel	50% Guy Distance		
	80% Guy Distance		



6 Meter System - Specifications

Fully Operational	Survivable	Mast i	ailure	
6 Meter 350G Mast				
Primary Guying Only Assumes tripod and guys are properly secured, soil conditions can greatly affect the holding capability of guy stakes				
	165 Lbs. Deployed			
Wind Sp	eed (mph)	70	90	
	30% Guy Distance			
1 Sq. Ft. Panel	50% Guy Distance	- "-		
	80% Guy Distance			
	30% Guy Distance			
2 Sq. Ft. Panel	50% Guy Distance			
	80% Guy Distance			
	30% Guy Distance			
3 Sq. Ft. Panel	50% Guy Distance			
	80% Guy Distance			
	30% Guy Distance			
4 Sq. Ft. Panel	50% Guy Distance			
	80% Guy Distance			

Fully Operational	Survivable	Mast i	ailure
6	6 Meter 350G Mast		
Primary & Secondary Guying Assumes tripod and guys are properly secured, soil conditions can greatly affect the holding capability of guy stakes			
1	L65 Lbs. Deployed		
Wind Spe	ed (mph)	70	90
	30% Guy Distance		
1 Sq. Ft. Panel	50% Guy Distance		
	80% Guy Distance		162
	30% Guy Distance		
2 Sq. Ft. Panel	50% Guy Distance		No. of Lot
	80% Guy Distance		
	30% Guy Distance		
3 Sq. Ft. Panel	50% Guy Distance	A vil	Silver .
	80% Guy Distance		
	30% Guy Distance		
4 Sq. Ft. Panel	50% Guy Distance	h E	
	80% Guy Distance	No. of Lot	

5 Meter System - Specifications

Fully Operational	Survivable	Mast F	aíture
5	Meter 350G Mas	t	
Primary Guying Only Assumes tripod and guys are properly secured, soil conditions can greatly affect the holding capability of guy stakes			
	L70 Lbs. Deployed	l	
Wind Spe	eed (mph)	70	90
	30% Guy Distance		
1 Sq. Ft. Panel	50% Guy Distance		
	80% Guy Distance		
	30% Guy Distance		
2 Sq. Ft. Panel	50% Guy Distance		
	80% Guy Distance		
	30% Guy Distance		
3 Sq. Ft. Panel	50% Guy Distance		
	80% Guy Distance		
	30% Guy Distance		
4 Sq. Ft. Panel	50% Guy Distance		
	80% Guy Distance		

Fully Operational	Survivable	Mast	Failure
5 Meter 350G Mast			
Primar	y & Secondary	Guving	
Assumes tripod and guys a	are properly secured, soil condit holding capability of guy stakes	tions can great	ly affect the
	170 Lbs. Deployed	l	
Wind Sp	eed (mph)	70	90
	30% Guy Distance		
1 Sq. Ft. Panel	50% Guy Distance		
	80% Guy Distance		
	30% Guy Distance		
2 Sq. Ft. Panel	50% Guy Distance		
	80% Guy Distance		
	30% Guy Distance		
3 Sq. Ft. Panel	50% Guy Distance		
	80% Guy Distance		
	30% Guy Distance		-
4 Sq. Ft. Panel	50% Guy Distance		
	80% Guy Distance		



4 Meter System - Specifications

Fully Operational	Survivable	Mast i	ailure	
4 Meter 350G Mast				
Primary Guying Only Assumes tripod and guys are properly secured, soil conditions can greatly affect the holding capability of guy stakes				
	175 Lbs. Deployed			
Wind Sp	eed (mph)	70	90	
	30% Guy Distance	H		
1 Sq. Ft. Panel	50% Guy Distance			
	80% Guy Distance			
	30% Guy Distance			
2 Sq. Ft. Panel	50% Guy Distance		البسيا	
	80% Guy Distance	استا		
	30% Guy Distance			
3 Sq. Ft. Panel	50% Guy Distance			
	80% Guy Distance			
	30% Guy Distance			
4 Sq. Ft. Panel	50% Guy Distance	تعظيا		
	80% Guy Distance			


Fully Operational	Survivable	Mast F	ailure	
4 Meter 350G Mast				
Primary & Secondary Guying Assumes tripod and guys are properly secured, soll conditions can greatly affect the holding capability of guy stakes				
	175 Lbs. Deployed			
Wind Sp	eed (mph)	70	90	
	30% Guy Distance			
1 Sq. Ft. Panel	50% Guy Distance			
	80% Guy Distance			
	30% Guy Distance			
2 Sq. Ft. Panel	50% Guy Distance	تسسيا		
	80% Guy Distance			
	30% Guy Distance			
3 Sq. Ft. Panel	50% Guy Distance			
	80% Guy Distance			
	30% Guy Distance	المساو		
4 Sq. Ft. Panel	50% Guy Distance			
	80% Guy Distance			

3 Meter System - Specifications


Fully Operational	Survivable	Mast F	ailure	
3 Meter 350G Mast				
	Primary Guying Only			
	re properly secured, soil condit holding capability of guy stakes		y arrect the	
	180 Lbs. Deployed			
Wind Spe	eed (mph)	70	90	
	30% Guy Distance			
1 Sq. Ft. Panel	50% Guy Distance			
	80% Guy Distance			
	30% Guy Distance			
2 Sq. Ft. Panel	50% Guy Distance			
	80% Guy Distance			
	30% Guy Distance		Water Company	
3 Sq. Ft. Panel	50% Guy Distance			
	80% Guy Distance			
	30% Guy Distance			
4 Sq. Ft. Panel	50% Guy Distance			
	80% Guy Distance			

Fully Operational	Survivable	Mast F	ailure
3 Meter 350G Mast			
Primar	y & Secondary	Guying	
	re properly secured, soil condit nolding capability of guy stakes		y affect the
4	180 Lbs. Deployed	l	
Wind Spi	eed (mph)	70	90
	30% Guy Distance		
1 Sq. Ft. Panel	50% Guy Distance		
	80% Guy Distance		
	30% Guy Distance		
2 Sq. Ft. Panel	50% Guy Distance		
	80% Guy Distance		
	30% Guy Distance		
3 Sq. Ft. Panel	50% Guy Distance		
	80% Guy Distance		
	30% Guy Distance		
4 Sq. Ft. Panel	50% Guy Distance		أنسطا
	80% Guy Distance		






350G XL Lift Series - 15M Datasheet (Case #1 of 2)





350G XL Lift Series - 15M Datasheet (Case #2 of 2)





Load / Unload 350G XL Lift Series Mast System Case





A total of six carry handles on corners and ends





Wheels on one end





Two-person lift and drag (lifted weight 76 lbs.)





Two-person lift one end onto vehicle / trailer (lifted weight 76 lbs.)



Load / Unload 350G XL Lift Series Mast System Case





Two-person lift one end onto vehicle / trailer





Two-person lift other end (lifted weight 76 lbs.)





Two-person slide case onto vehicle / trailer





Case loaded for transport, reverse process for unloading



Deploying the 350G XL - Lift Series Mast System With Primary and Secondary Guying

Expert Users - 2 People - 25 Minutes

Novice Users - 2 People - 45 Minutes



1) Inspecting the Site Before Deployment.

- A) Make sure the ground where you are deploying is level, clear of debris and is capable of holding the tripod stakes and guy stakes.
- B) Make sure there is enough room to extend your guy ropes out to the full length based on your deployment height. BlueSky Mast recommends an 80% guy radius.
- ⚠ C) SAFETY: Make sure there are no overhead wires, buried power lines, or an unexploded ordinance.

2) Setting Up and Orienting the Tripod.

- A) Locate the Tripod in Hard Case One and stand the tripod up on the ground with the Tilt Leg (opposite the winch) facing in the same direction that you want your equipment to point.
- B) Loosen the red turn knobs on the cross links of each tripod leg to extend the legs.





- C) Slowly push down on the red turn knobs while pulling the leg out to extend it.
- D) Push the cross links all the way down and tighten the turn knobs to secure them.








3) Extending the Two Tripod Legs opposite the Tilt Leg.

- A) One at a time, fully extend the two tripod legs adjacent to the winch by loosening the turn knobs on the tripod legs. **DO NOT EXTEND** the Tilt Leg, opposite the winch at this time.
- B) Once fully extended, lock them in place by tightening the turn knobs on each leg.







- C) Make sure all tripod base plates are level and flat on the ground.
- D) Locate the stake bag with the tripod stakes and hammer.
- E) Drive a **SINGLE** tripod stake at a slight angle into the **LEFT SIDE** of each of the two base plates on the **TWO EXTENDED LEGS ONLY**. Do not drive a stake into the right side of the base plates at this time.







4) Inserting the Mounting Pole.

- A) Release the Cam Lock on the bottom of the tripod.
- B) Locate the Mounting Pole in Hard Case #2. (The Mounting Pole is the only pole without a gold insert).
- C) Insert it into the top of the tripod with the castle cut on the bottom of the pole until the first hole on the Mounting Pole is visible below the Cam Lock, then lock the Cam Lock.








5) Cam Lock Maintenance

- **A** A) SAFETY: If at any point the mast begins to slip while the Cam Lock is engaged, use the wrench provided with the system to make adjustments.
 - B) If slipping occurs after center mast poles have been deployed, lower the mast so that it contacts the ground.
 - C) Tighten the nut on the Cam Lock a quarter of a turn until slipping no longer occurs.








6) Adding the Primary and Secondary Guy Ring.


- A) Locate the Blue Secondary Guy Ring located in the bag marked GUYING.
- B) Release the Cam Lock on the Blue Secondary Guy Ring and slide it over the top of the mounting pole until it rests on top of the tripod. **DO NOT** lock it into place at this time.





- C) Locate the **Red Primary Guy Ring** located in the bag marked GUYING.
- D) Remove the push pin and slide it over the top of the Mounting Pole until it rests on top of the Blue Secondary Guy Ring. **DO NOT** pin the Red Primary Guy Ring at this time.









7) Attaching Your Equipment.


- A) Attach your equipment to the Mounting Pole.
- B) Properly adjust and secure your equipment and connect any cables at this time.
- ⚠ C) SAFETY: Always secure loose cables to the mast during deployment with Velcro or some form of cable management to reduce strain on the cables and prevent damage to the connections. Loose cables can also cause the mast to lean to one side and affect performance and safety.






8) Raise the Tilt Leg.

- A) Loosen the Turn Knob on the Tilt Leg.
- B) Push the tripod upright and then extend the Tilt Leg fully.
- C) Tighten the Turn Knob.









9) Leveling the Tripod.

- A) Make sure all Tripod Base Plates are level and flat on the ground.
- B) Locate the three Bubble Levels on the Tripod.
- C) If any of the bubbles fall beyond the level lines, one at a time, loosen the turn knob on the leg and adjust the length as needed to make the tripod level. Tighten the turn knobs when finished.
- A D) SAFETY: Improper leveling can result in excessive leaning which can damage the system and can cause serious bodily harm.



10) Securing the Tripod.

A) Drive tripod stakes in at a slight angle (opposite directions) into the remaining holes on all three tripod leg base plates.





11) Attaching the Winch Handle.

- A) Locate the Winch Handle (located in the large black accessory bag).
- B) Pull the Quick Release Pin on the front of the Winch. Slide the Winch Handle into the slot. Release the pin and lock the handle into place.







12) Attaching the Lift Base Plate.

- A) Locate the Lift Base Plate (located in the large black accessory bag).
- B) Insert it into the bottom of the Mounting Pole.
- C) Align the Lift Base Plate so that the rollers on the plate are in line with the Winch and the Tilt Leg.









13) Attaching and Securing the Winch Cable.

- A) Turn the Winch Handle counter-clockwise paying out about three feet of cable.
- B) Make sure the cable extends directly from the bottom left side of the winch reel.DO NOT let the cable loop over the spacer, it must hang freely form the winch.
- A) Pass the end of the cable with the Ball Stop through the bottom of the two rollers on the Lift Base Plate.





- D) Locate the Ball Stop Holder located on the bottom of the Tripod opposite the Winch.
- E) Secure the Ball Stop by pulling the pin on the Ball Stop Holder and guide the Ball Stop into place.
- ▲ F) SAFETY: After releasing the pull pin on the Ball Stop Holder, tug on the cable to make sure it is securely in place.
 - G) Remove the slack in the cable by cranking the winch handle clockwise until the Lift Base Plate is seated securely in the bottom of the Mounting Pole.









14) Confirm the tripod is level and secured.

- A) If any of the bubbles fall beyond the level lines, one at a time, loosen the turn knob on the tripod leg and adjust the length as needed to make the tripod level.
- B) Fully tighten the Tripod Leg Turn Knobs.
- ⚠ C) SAFETY: Never adjust the Tripod Leg Turn Knobs during or after deployment of the Center Mast Poles.





15) Raising the Mounting Pole.

- A) Make sure that the cable is taut and the Lift Base Plate is secure in the bottom of the Mounting Pole.
- B) Release the Cam Lock on the bottom of the tripod.
- C) Raise the Mounting Pole by cranking the winch handle clockwise until the bottom of the Mounting Pole is within one inch of the bottom of the tripod.
- D) Secure the Mounting Pole by locking the Cam Lock on the tripod.
- ▲ E) SAFETY: When raising the poles, make sure there is always one inch of the pole visible beneath the bottom of the tripod before securing the Cam Lock.











16) Securing the Primary Guy Ring.

A) Pin the Red Primary Guy Ring to the Mounting Pole below your equipment. Make sure to allow enough room for the Primary Guys to be deployed without interference.






17) Deploy Primary Guying - 2 ppl (4 Guy Configuration)

- A) PERSON #1 Locate the GUY LEADER with Orange Guy Rope
- B) Clip the end into the Round Hole on the Red Primary Guy Ring.
- C) Walk away from the mast unwinding the guy rope until you reach to 15M mark on the guy leader.








17) Deploy Primary Guying - 2 ppl - Continued...


D) PERSON #2 - Locate the 4 Large Guy Stakes and hammer and follow Person #1



- E) Guy Stake #1 At the 15M mark on the Guy Leader, drive a stake into the ground at an angle.
- F) Guy Stake #2—make sure it is staked directly opposite and inline with Guy Stake #1 at the 15M mark on the Guy Leader.
- G) Repeat this process until all 4 guy stakes have been deployed 90 degrees apart.










17) Deploy Primary Guying (I DO NOT HAVE A GUY LEADER)

NOTE: If you have lost or do not have a GUY LEADER to mark your guy stakes, start at the center of the tripod and take One NORMAL Step per meter of system height away from the mast. Do not exaggerate your steps, take one NORMAL step per meter of height.


EXAMPLE: 15M = 15 NORMAL Steps. Person #1 should be the only person doing this to ensure each of the 4 guy stakes are deployed at similar distances.




18) Primary Guying - Deploying the 1st Primary Guy Rope.

- A) Locate the 4 Primary Guy Ropes with Red Tabs next to the guy clip.
- B) Remove the guy leader and clip the first primary guy rope to the round hole on the primary guy ring.
- C) Unwind the guy rope from the guy handle while walking away from the mast and towards the first guy stake.











18) Primary Guying - Continued...


- D) Make sure to unwind all of the guy rope off the guy handle and clip the primary guy rope to the top hole of the guy stake.
- E) **IMPORTANT:** Slide the guy handle towards the mast approx. 7 feet. This will help to prepare you for incremental guying.






19) Primary Guying - Deploying the Remaining Primary Guy Ropes.

- A) Attach the stainless steel clip on the free end of the Primary Guy Ropes to the remaining **Square Holes on the Primary Guy Ring**.
- B) Repeat the process outlined in step 18 until all 4 guy ropes have been deployed.
- C) When finished, the Primary Ropes should be deployed 90 degrees from each other.







20) Lowering the Lift Base Plate to the Ground.

- **A** A) SAFETY: Make sure the Cam Lock is locked before lowering the lift base plate.
 - B) Slowly begin lowering the Lift Base Plate by turning the winch handle counter clockwise making sure that the Mast Poles do not begin to move.
- ⚠ C) SAFETY: If slipping occurs check that the Cam Lock is locked. If it is locked, refer to the "Cam Lock Maintenance" on Page 24.
 - D) Continue lowering the Lift Base Plate until it rest flat on the ground.





21) Inserting the First Center Mast Pole.

- A) Locate a Center Mast Pole (with the gold insert) in Hard Case #2 and insert the bottom of the Center Mast Pole onto the tapered cone of the Lift Base Plate.
- B) THIS IS A ONE PERSON OPERATION Slowly crank the winch handle with one hand while using the other hand to gently guide the gold insert of the Center Mast Pole into the bottom of the Mounting Pole.







21) Inserting the First Center Mast Pole - Continued...

B) Make sure the poles nest together fully and no gold is showing in the seam.



22) Lifting the Center Mast Pole.

- A) Make sure that the cable is taut and straight. If the cable has become slightly twisted then tap the Lift Base Plate lightly with your foot to straighten out the cable.
- B) Release the Cam Lock and raise the Center Mast Pole until the bottom is within one inch of the bottom of the tripod.
- C) Lock the Cam Lock on the tripod.
- D) Repeat this process of adding Center Mast Poles until it is time to engage the Blue Secondary Guy Ring at one half the total mast height.







HELPFUL HINTS:

Guide the cable on the winch to avoid stack up and jumping.

Secure all cables using the Velcro Straps

Always monitor your Guy Wires




23) Secondary Guying - Securing the Secondary Guy Ring.

- A) When you have deployed the mast half way, stop and lock the Cam Lock on the bottom of the tripod. *Helpful Hint: A 15M system has 14 poles*.
- B) Locate the Blue Secondary Guy Ring on top of the tripod and lock the Cam Lock.
- ⚠ C) SAFETY: Make sure that the Cam Lock is fully locked and that the safety is covering the Cam Lock Lever. This will prevent a guy rope from accidentally unlocking the Blue Secondary Guy Ring during deployment.







24) Secondary Guying - Deploying the Secondary Guy Ropes

- A) Locate the four Secondary Guy Ropes with Blue Tabs next to the guy clip in the bag marked GUYING.
- B) Attach the stainless steel clip on the free end of the 1st Secondary Guy Rope to the round hole on the Blue Secondary Guy Ring.







24) Secondary Guying - Continued...

- C) Walk away from the mast while unwinding ALL of the guy rope from the handle.
- D) Clip the end of the secondary guy rope to the bottom hole on the guy stake.
- E) Repeat the Process until all 4 Secondary Guy Ropes have been deployed using the remaining square holes on the secondary guy ring








25) Continue to raise the Mast Poles - Incremental Guying may be required.

- A) SAFETY: If at any point the mast begins to slip while the Cam Lock is engaged, use the wrench provided with the system to make adjustments.
 - B) If slipping occurs after center mast poles have been deployed, lower the mast so that it contacts the ground.
 - C) Tighten the nut on the Cam Lock a quarter of a turn until slipping no longer occurs.








Incremental Guying - Why is it Important?


Heavy loads or windy conditions can exert extra force on the center mast poles during deployment causing them to bind in the tripod and create potentially unsafe conditions. Incremental Guying is used when the mast begins to lean and is no longer straight and perpendicular.

Incremental guying may be required when less than two people are available to hold the primary or secondary guy ropes during deployment with heavy loads or high winds.

Excessive leaning during deployment is an indicator that incremental guying is required. When these conditions exist, it will be necessary to incrementally guy the mast during deployment before reaching the desired height. Incremental guying will add time to the deployment but will ensure the safety of both personnel and equipment

Be sure when adjusting the amount of tension on the guy ropes not to over tighten the guy ropes. This puts significant downward pressure on the mast. See the diagram below for reference on how guy ropes and the mast should look when correctly deployed.







HELPFUL HINTS:

Guide the cable on the winch to avoid stack up and jumping.

Secure all cables using the Velcro Straps


Always monitor your Guy Wires


BLUESKY MAST



26) Incremental Guying - 2 ppl.

- A) Once the mast begins to lean or the Primary Guy Ropes go taut, then stop cranking the winch and Lock the Cam Lock
- B) Person #1 should go to the Guy Rope opposite the direction the mast is leaning.
- C) Person #2 should go to the guy rope that is 90 degrees from person #1.
- D) To adjust the guy rope, hold the rope in front of the guy handle and slide the handle forward to tighten or use your finger to release the rope from the cleat to slide the handle back and loosen.
- E) Adjust all 4 primary guy ropes until the mast is straight and perpendicular.







F) Now loosen the primary guy ropes (based on the length of the pole below the cam lock). See examples below. If the length of the pole under the cam lock is 1 foot - slide the handle back 1 foot on each of the 4 primary guy ropes. This will allow you enough room to raise the mast 1 foot and prepare for the next mast pole.










26) Incremental Guying - Continued...

- G) Release the cam lock and raise the mast until 1 inch is showing under the cam lock.
- H) Lock the cam lock.
- I) Make sure all 4 primary guy ropes are taut and the mast is straight.








- J) Lower the lift base plate to the ground and insert another mast pole.
- K) Raise the mast pole until the castle cuts nest together.
- L) Now adjust all 4 primary guy ropes by sliding the handle back approx. 4 feet.
- M) This will allow you enough slack to add another mast pole.

NOTE: The mast will lean, but will straighten up as you raise the next mast pole.







Repeat the process outlined in step # 26 until you have reached the last center mast pole.





27) Deploying the last center mast pole.


- A) Insert the bottom of the last mast pole onto the Lift Base Plate.
- B) Raise the mast pole until it nest into the previous mast pole.
- C) Release the came lock and slowly lower the mast pole to the ground.
- D) Lock the cam lock.







28) Adjusting the Primary Guy Ropes (2 ppl)

- A) If the mast is leaning, Person #1 should go to the guy rope opposite the lean.
- B) Person #2 should go to the guy rope that is 90 degrees from person #1. This will allow you to see how far each guy rope needs to be adjusted to get the mast straight and perpendicular. Rotate to the other guy ropes to continue adjustment.
- C) It may take a coupe rotations on the guy ropes to get the mast straight and perpendicular









29) Adjust and Lock the Primary Guy Ropes.

A) Lock the Primary Guy Ropes by holding the rope in front of the handle and sliding the handle slowly towards the mast allowing the rope to settle into the cleat which will lock the rope into position



30) Adjust and Lock the Secondary Guy Ropes


A) Repeat the process above for the secondary guy ropes.





31) Stake the Lift Kit Base Plate

- A) Make sure the mast is straight and perpendicular and the primary and secondary guy ropes are adjusted and locked.
- B) Using your foot gently tap on the mast pole to help relevel the mast (check bubble levels).
- C) Drive two stakes into the lift kit base plate to secure it.









32) Deploy the Surface Wire Grounding Kit. (Optional)

A) The BlueSky Surface Wire Grounding Kit (additional accessory) can be deployed at this time if available when lightning or static discharge is a safety concern.



33) Stow the Equipment and Secure the Area.

- A) Police the area for any loose tools or equipment that may have been left in the field during deployment.
- B) Stow the Hard Cases in a safe place for easy retrieval.





Lowering / Recovery 350G XL - Lift Series Mast System Primary & Secondary Guying

Expert Users - 2 People - 25 Minutes

Novice Users - 2 People - 45 Minutes




1) Removing the Lift Base Plate Stakes.

A) Locate the Crow Bar or Stake Pullers included with the system and remove the two stakes from the lift kit base plate.



2) Loosening the Primary and Secondary Guy Ropes

- A) Unlock the Primary and Secondary Guy Ropes and slide the Handle away from the mast approx. ONE FOOT (12 Inches)
- B) DO NOT loosen the guy ropes more than ONE FOOT (12 inches)
 One foot (12 inches) is all you need to raise the mast and remove the first mast pole.



3) Raising the Mast Pole.

- A) Release the Cam Lock
- B) Raise the mast approx. one foot (12 inches) by SLOWLY turning the Winch Handle clockwise until there is only one inch of the top of the mast pole visible below the cam lock.
- C) Lock the Cam Lock








4) Removing the Mast Pole.

⚠ A) SAFETY: Make sure the Cam Lock is engaged before lowering the Lift Base Plate.

B) Lower the Mast Pole to the ground by SLOWLY turning the Winch Handle counter clockwise until the Lift Base Plate rests firmly on the ground.








4) Removing the Mast Pole - Continued...


- C) Step on the lift base plate, remove the Mast Pole and stow it in the Hard Case.
- D) Raise the Lift Base Plate until it nests firmly into the bottom of the next Center Mast Pole and the cable is straight and taut.





5) Lowering the Mast - Removing the Next Center Mast Pole.

- A) Release the Cam Lock and SLOWLY lower the mast until one inch of the next mast pole is showing below the cam lock. The mast will begin to lean.
- B) Lock the cam lock, remove the mast pole and store it in Hard Case #2
- C) Raise the lift kit base plate until it nests firmly into the next mast pole.
- D) SEE NEXT STEP ADJUSTING THE PRIMARY GUY ROPES











Incremental Guying is **MANDATORY** when lowering the first 3 - 5 center mast poles.

6) Adjusting the 4 Primary Guy Ropes- 2 ppl.

- A) Person #1 should go to the Guy Rope opposite the direction the mast is leaning.
- B) Person #2 should go to the guy rope that is 90 degrees from person #1.
- C) Adjust the Primary Guy Ropes by holding the rope in front of the guy handle and sliding the handle forward to tighten.
- D) Adjust all 4 primary guy ropes until the mast is straight and perpendicular.








7) Lowering the Next Center Mast Pole.

- A) Release the Cam Lock and SLOWLY lower the mast until one inch of the next mast pole is showing below the cam lock.
- B) Lock the cam lock, remove the mast pole and store it in Hard Case #2
- C) Raise the lift kit base plate until it nests firmly into the next mast pole.











8) Adjusting the 4 Primary Guy Ropes- 2 ppl.

- A) Person #1 should go to the Guy Rope opposite the direction the mast is leaning.
- B) Person #2 should go to the guy rope that is 90 degrees from person #1.
- C) Adjust the Primary Guy Ropes by holding the rope in front of the guy handle and sliding the handle forward to tighten.
- D) Adjust all 4 primary guy ropes until the mast is straight and perpendicular.
- E) REPEAT STEPS 7 & 8 UNTIL YOU REACH THE SECONDARY GUY RING







- **A**) SAFETY: If at any point the mast begins to slip while the Cam Lock is engaged, use the wrench provided with the system to make adjustments.
 - B) If slipping occurs after center mast poles have been deployed, lower the mast so that it contacts the ground.
 - C) Tighten the nut on the Cam Lock a quarter of a turn until slipping no longer occurs.








350G XL Lift Series - Mast Lowering / Recovery

9) Removing the Secondary Guy Ropes.

- A) When the Blue Secondary Guy Ring reaches the top of the tripod, stop lowering the mast.
- B) Disconnect the Secondary Guy Ropes, pull in all the slake and wind the loose rope back onto the handle, then place them into the bag marked GUYING.

C) Release the Cam Lock on the Blue Secondary Guy Ring and allow it to rest on top of the Tripod.



10) Removing the Primary Guy Ropes.

- A) Continue lowering the mast until the Red Primary Guy Ring is easily within reach.
- B) Remove the Primary Guy Ropes, pull in all the slake and wind all of the rope onto the handle and place all 4 into the bag marked GUYING.





350G XL Lift Series - Mast Lowering / Recovery


11) Remove the Guy Stakes

- A) Use the hammer to tap each side of the stake & front and back to loosen and remove the stakes.
- B) Place the stakes back into the large stake bag.



12) Lowering the Tripod.

- A) Use the Crow Bar or Stake Puller to remove both stakes in the Tilt Leg Base Plate opposite the winch.
- B) Use the Crow Bar or Stake Puller to remove a single stake on the right side of each of the remaining two base plates.
- C) Loosen the Turn Knob on the Tilt Leg of the Tripod and gently allow the tripod to kneel until the Tilt Leg has been fully collapsed.










350G XL Lift Series - Mast Lowering / Recovery

13) Remove and Stow Devices and Guy Rings.

- A) Remove all devices and accessories from the mounting pole.
- B) Remove the Red Primary Guy Ring and Blue Secondary Guy Ring and stow them in the bag marked GUYING.





14) Removing the Remaining Equipment.

- A) Release the Winch Cable from the Ball Stop Holder and wind the cable back onto the Winch and stow the Handle and Lift Base Plate in the black accessory bag.
- B) Release the Cam Lock and Place the Mounting Pole into Hard Case #2.
- C) Lock the cam lock
- D) Remove the remaining Tripod Stakes and put them back in the stake kit bag.
- E) Collapse the two extended Tripod Legs and tighten the turn knobs.









350G XL Lift Series - Stowing and Packing the System

15) Collapse and stow the tripod.

- A. One at a time loosen the red turn knobs on the cross links and slowly pull up on the red turn knob while pushing the leg inward.
- ⚠ B. SAFETY: PINCHING HAZARD When collapsing the tripod, DO NOT put your fingers in the cross links.







C) Tighten the red turn knobs to secure the tripod legs and stow the tripod in case #1




16) Stow Loose Gear and Police the Area.

A) Stow any loose gear. SEE NEXT PAGE "Stowing & Packing the System" Diagram for further instructions.



350G XL Lift Series - Stowing and Packing the System


15M System - HARD CASE #1





350G XL Lift Series - Stowing and Packing the System

15M System - HARD CASE #2



MOUNTING POLE

CENTER MAST POLES



BLUESKY WAST elevating solutions

www.blueskymast.com | 877-411-6287







Top Plates & Adaptors

These items include a pin on adaptor to mount on top of our AL3 mast system.



OE-254 & COM201 Antennas BSM3-K-M400-0E2-000



Manual Tilt Assembly with Mounting Pole BSM3-K-M650-TLT-000



Pan & Tilt for Oulckset OPT & FLIR

BSM3-A-M460-MPP-00A





Cross Pattern 6 x 6 BSM3-A-M550-MPP-00A



Cross Pattern 8 x 10 BSM3-A-M408-MPP-00A





NATO-SINCGARS-EPLRS BSM3-A-M305-NTO-00A





Solid 7.5 x 7.5 Inch BSM3-A-M407-MPP-00A





BSM3-A-M411-MPP-00A



Radar 8 x 11 Inch BSM3-A-M400-MPP-RDA



www.blueskymast.com | 877-411-6287







Top Plates & Adaptors

These items include a pin on adaptor to mount on top of our AL3 mast system.



KVH TracPhone TPV 3-7, TVHD 11 BSM3-K-M309-MPP-TRC





Cisco 1500 Series BSM3-A-M410-CSC-00A





Tampa Microwave BSM3-A-M410-MPA-TML



G2 Magnetic Mount BSM3-A-M325-MAG-00A



BMS GPS & RF Tracking, GTA 17/58 BSM3-A-M365-BMS-00A





TCS SwiftPoint 360 BSM3-A-M500-TCS-00A





PSL-DF Device BSM3-A-M415-MPP-00A





Pin On Threaded Adapter BSM3-P-M510-PIN-000





Mobile Mark Omni Antenna BSM3-A-M718-MPP-00A











Side Arm Kits

These Side Arm Kits can be mounted anywhere on an AL3 mast system (Based on system height and payload).

STRAIGHT ARM KIT - DUAL - COM201/0E-254





(1) Side Arm Mount - 1.5 in. COM201 / OE-254 P/N: 85M3-K-M400-0E2-EM0

(1) AL3 Pole Mount - Two sided P/N: BSM3-P-A352-T00-100



This kit includes two insulated adaptors that work with both COM201 and OE-254 antennas.

ARM LENGTH	PART NUMBER		
48 in.	BSM3-K-A352-S48-0E2		

(2) Straight Arm Bracket w/1.5 in. Side Arm (48 in.) P/N: BSMU-P-A344-ARM-15S

STRAIGHT ARM RET - DUAL - NATO








PAN: BSM3-A-M305-NTO-EMO




(1) Side Arm Mount – 1 in. NATO-SINGARS-EPLRS (2) Straight Arm Bracket w/1.5 in. Side Arm (24, 36, 48 in.)

www.blueskymast.com | 877-411-6287







Side Arm Kits

These Side Arm Kits can be mounted anywhere on an AL3 mast system (Based on system height and payload).





(1) AL3 Pole Mount - Two Sided P/NEBSM3-P-A352-T00-000

(2) Straight Arm Bracket w/1.5 in. Side Arm (6 to 48 in.)
P/M: BSMU-P-A3XX-ARM-15S
NOT INCLUDED: 1.5 in. Side Arm Mount (See optional side arm mounts)

STRAIGHT ARM KIY - SINGLE - NO SIDE MOUNT

ARM LENGTH (inches)	PART NUMBER			
6 in.	8SM3-K-A351-S06-150			
12 in.	BSM3-K-A351-S12-150			
24 in.	BSM3-K-A351-524-150			
36 in.	BSM3-K-A351-S36-150			
48 ln.	BSM3-K-A351-548-150			







(1) AL3 Pole Mount - Two Sided P/N: BSM3-P-A3S2-Too-000

(2) Straight Arm Bracket w/1.5 in. Side Arm (6 to 48 in.)
P/M: BSMU-P-A3XX-ARM-15S
NOT INCLUDED; 1.5 in. Side Arm Mount (See optional side arm mounts)

STRAIGHT ARM KIT - DUAL - NO SIDE MOUNT

ARM LENGTH (indies)	PART NUMBER
6 i n.	BSM3-K-A352-S06-150
12 in.	BSM3-K-A352-S12-150
24 in.	BSM3-K-A352-S24-150
36 in.	BSM3-K-A352-S36-150
48 in.	85M3-K-A352-S48-150

HREWAY



(1) AL3 Pole Mount - Sided P/N: BSM3-P-A352-T00-000

(3) Straight Arm Bracket w/1.5 in. Side Arm (6 to 48 in.)

P/N: BSMU-P-A3XX-ARM-15S

NOT INCLUDED: 1.5 in. Side Arm Meunt (See optional side arm mounts)

STRAIGHT ARM KIT - THREE WAY - NO SIDE MOUNT

ARM LENGTH (inches)	PART NUMBER BSM3-K-A353-506-150		
6 in.			
12 in.	85M3-K-A353-512-150		
24 in.	BSM3-K-A353-524-150		
36 in.	BSM3-K-A353-S36-150		
48 in.	BSM3-K-A353-544-150		

elevating solutions

www.blueskymast.com | 877-411-6287







Side Arm Mounts

These Side Arm Mounts can be used with all AL3 side arm kits (Based on system height and payload).





Adjust to fit antennas with an OD of .75 to 2.0 inches

Omni Antenna .75 to 2.0 Inch BSMU-P-A112-OMN-EMS





Adjust to fit antennas with an OD of 2.0 to 3.5 inches

Omni Antenna 2.0 to 3.5 Inch BSMU-P-A350-OMN-EMS





NATO - SINGARS - EPLRS BSMU-A-M305-NTO-EMS





OE-254 & COM201 Antennas BSMU-K-M400-OE2-EM5

This insulated adaptor works with both COM201 and OE-254 antennas.









Side Arm Mounts

These Side Arm Mounts can be used with all AL3 side arm kits (Based on system height and payload).



Cross Pattern 8x10 BSMU-A-M408-MPP-EM5



Cisco 1500 Series BSMU-A-M410-CSC-EMS



Solid 7.5x7.5 BSMU-A-M407-MPP-EM5



Bolster Plate BSMU-P-A101-BOL-EM5



ARUBA AP BSMU-A-M325-AAP-EM5



Solid 11.5x11.5 BSMU-A-M411-MPP-EM5



L-Com Mimo Omni Antenna BSMU-A-M454-MPP-EM5



G2 MAG MOUNT BSMU-A-M325-MAG-EMS



GPS Antenna BSMU-A-M375-GPS-EM5

BLUESKY MAST elevating solutions

www.blueskymast.com | 877-411-6287

Pole Mounts & Plate Brackets

BlueSky Mast's patented interface (slide lock technology) allow warfighters to easily attach and remove devices to our universal pole mount, which can be secured anywhere on the mast from the base to the top.

















POLE MOUNTS U.S. and International Palents Pending

Position anywhere on the mast, secure by latching and tightening the turn knobs. Plates w/Brackets can now be added.

Pole Mount - Two Sided - AL3 BSM3-P-A352-T00-000







Patented BlueSky Mast Interface







Pole Mount - Three Sided AL3 - BSM3-P-A353-T00-000







Patented BlueSky Mast Intérface
















Plate Brackets

These plate brackets can be mounted anywhere on the mast using our 2 or 3 side pole mounts.

FRONT OF PLATE









BACK OF PLATE

PLATE BRACKET ON POLE MOUNT

Patented BlueSky Mast Interface



Universal PTP Plate BSM2-A-M900-PTP-BRK



Cisco Aironet 1520 Series 85M2-A-M524-CSC-BRK



Omni Bracket .75 to 2.0 Inch OD BSMU-P-A112-OMN-BRK



Ultra TCS 245 Radio BSMU-A-M850-TCS-BRK



Omni Bracket 2.0 to 3.5 Inch OD BSMU-P-A350-OMN-BRK



Cross Pattern 8x10 Inch BSM2-A-M408-MPP-BRK









Plate Brackets

These plate brackets can be mounted anywhere on the mast using our 2 or 3 side pole mounts.



GD Fortress ES Series 8SM2-A-M520-GDF-BRK



Ultra TCS Antennas BSMU-P-A860-TCS-BRK



Cambium/Motorola Radio & LPU BSM2-A-M41S-MOT-BRK



Hoffman NEMA Endosures BSM2-A-M412-HFM-BRK



Radiowaves 2ft. Parabolic Antenna BSM2-A-M502-MPP-BRK



Mobile Mark 120 Sec Antenna BSMU-A-M710-MMA-BRK



Tampa Micro Satellite Simulator BSM2-A-M410-MPA-TM2



Rajant Ethemet Radio BSMU-A-M585-RAJ-BRK



AirGrid M Antennas BSM2 -A-M560-MPP-BRK









Plate Brackets

These plate brackets can be mounted anywhere on the mast using our 2 or 3 side pole mounts.

000000000000

PCTel Sector Antenna SP4959 BSMU-A-M705-PCT-BRK



Hyperlink - L-Com Panel Antenna BSM2-A-M700-MPP-BRK



GD V6 eNode B BSMU-A-M411-EN6-BRK



Rajant Breadcrumb Radio BSMU-A-M580-RAJ-BRK



Solid 7.5x7.5 BSM2-A-M407-MPP-BRK



Solid 11.5x11.5 BSM2-A-M411-MPP-BRK




Rajant PC Tel Sector Antenna BSMU-A-M587-RAJ-BRK



BKT-11 QUAD and MPU3 BSM2-A-M811-BKT-BRK



C2M2 Transceiver BSMU-A-M525-C2M-BRK




elevating solutions

www.blueskymast.com | 877-411-6287

Certified Grounding & Lightning Protection

Protect your equipment with grounding and lightning components from BlueSky Mast.

FOLNOING



Surface Wire Grounding Kit - AL3 BST3-K-L104-GND-000



ICHTNING PROTECTION



Pin On Lightning Air Terminal - AL3 BST3-K-L102-GND-000



Blue Sky Mast

elevating solutionsSM

BlueSky Mast Inc 1515 Gunn Hwy Odessa, FL 33556 USA

Phone: 877-411-6278

FAX: 866-411-6278

sales@blueskymast.com www.BlueSkyMast.com

Cage Code: 3JWX5

DUNS Number: 137469404

		,	